



## **ADDENDUM NO. 1**

**TO  
BID PROPOSAL  
AND SPECIFICATIONS  
FOR**


### **Delta Fair Boulevard Pavement Reconstruction P.W. 439-3**

**ISSUED: January 27, 2011**

**This Addendum No. 1 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.**

**SEE ATTACHED ADDENDUM ITEMS**

Prepared By:

  
\_\_\_\_\_  
Ahmed Abu-Aly, P.E.

#### **BIDDER'S CERTIFICATION**

**I acknowledge receipt of this Addendum No. 1 and accept all conditions contained herein.**

\_\_\_\_\_  
**Bidder's Signature**

\_\_\_\_\_  
**Date**

\_\_\_\_\_  
**Name of Company**

**ADDENDUM NO. 1: Delta Fair Boulevard Pavement Reconstruction  
P.W. 439-3**

**ISSUED: January 27, 2011**

Special Provision:

**Item 1: Add Section C-19: POLYESTER PAVING MAT**

This work shall consist of finishing and installing a fiberglass polyester paving mat produced by Owens Corning or approved equal. The paving mat shall be Type I and shall meet the standard specification ASTM D5035 for Geosynthetic Paving Mat.

The paving mat shall be placed per the manufacturer's recommendations.

The contract unit price paid per square yard for the paving mat shall include full compensation for finishing and labor, materials, tools, equipment and incidentals and for doing all the work involved in finishing and placing paving mat as shown in the plans and per the manufacturer's installation guidelines and as directed by the Engineer.

**Item 2: Section C-17: Asphalt Concrete Plug Alternate "A": shall be amended as follows:**

For Alternate "A" the contractor shall stage his operation to complete the full 6" grind and the 4" AC plugs for each section in the same day, all lanes shall be open for public traffic at the end of the day. Full compensation for 6" grinding of the existing AC and the roadway section, shall be included in the contract unit price per ton for 4" Asphalt Concrete plug for Alternate "A".