



ADDENDUM NO. 2
TO
SPECIFICATIONS
FOR
COUNTRY HILLS DRIVE
SANITARY SEWER MAIN REHABILITATION
IN
ANTIOCH, CALIFORNIA
P.W. 545-1

ISSUED
July 1, 2014

This Addendum No. 2 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.

SEE ATTACHED ADDENDUM ITEMS

Prepared By: 
Scott Buening, P.E.



BIDDER'S CERTIFICATION

I acknowledge receipt of this Addendum No. 2 and accept all conditions contained herein.

Bidder

By:

- 1) Item 'A' of Section 02145, "Sewer Flow Control", Subsection 3.05, "Sewage Flow Control and Diversion", is amended to state the following:

"Prior to performing the first installation of lining work on the project, the Contractor shall set up and test the sewage flow bypassing system for a minimum period of one hour, between the hours of 8:00 a.m. and 9:00 a.m., or as directed by the Engineer. The Contractor shall correct any deficiencies in the system as required to provide a leak-free bypassing that will not cause overflows, back-ups or spills, as specified."

- 2) Item 'A' of Section 02145, "Sewer Flow Control", Subsection 3.06, "Pressure Testing of Pipelines", is amended to state the following:

"Prior to performing the first installation of lining work on the project and prior to bypassing any sewage, the proposed bypass system shall be pressure tested using potable water to 100% of working pressure. Pressure shall hold within 3 psi for a minimum of 15 minutes."